

Overview of the LhARA Facility

Review of the LhARA pre-CDR

Ajit Kurup

25th March 2020



**Imperial College
London**

Introduction

- Overview of the design of the facility.
 - Design parameters.
 - Accelerator
 - End stations
 - Diagnostics
- Staging.
- R&D plan and project schedule.


Design parameters

Parameter	Value or range	Unit
Laser driven proton and ion source		
Laser power	100	TW
Laser Energy	1	J
Laser pulse length	30	fs
Laser rep. rate	10	Hz
Proton energy	15	MeV
Proton and ion capture		
Beam divergence to be captured	50	mrad
Gabor lens effective length	0.857	m
Gabor lens length (end-flange to end-flange)	1.157	m
Gabor lens cathode radius	0.0365	m
Gabor lens maximum voltage	65	kV
Number of Gabor lenses	2	
Alternative technology: solenoid length	1.157	m
Alternative technology: solenoid max field strength	1.3	T
Stage 1 beam transport: matching & energy selection, beam delivery to low energy end station		
Number of Gabor lenses	3	
Number of re-bunching cavities	2	
Number of collimators for energy selection	1	
Arc bending angle	90	Degrees
Number of bending magnets	2	
Number of quadrupoles in the arc	6	
Alternative technology: solenoid length	1.157	m
Alternative technology: solenoid max field strength (to serve the injection line to the Stage 2)	0.8 (1.4)	T

Design parameters


Parameter	Value or range	Unit
Stage 2 beam transport: FFA, transfer line, beam delivery to high-energy endstations		
Number of bending magnets in the injection line	7	
Number of quadrupoles in the injection line	10	
FFA: Machine type	single spiral scaling FFA	
FFA: Extraction energy	20-127	MeV
FFA: Number of cells	10	
FFA: Orbit R _{min}	2.92	m
FFA: Orbit R _{max}	3.48	m
FFA: External R	4	m
FFA: Number of RF cavities	2	
FFA: RF frequency	1.46-6.48	MHz
FFA: spiral angle	48.7	Degrees
FFA: Max B field	1.4	T
FFA: k	5.33	
FFA: Magnet packing factor	0.34	
FFA: Magnet gap	0.047	m
FFA: Number of kickers	2	
FFA: Number of septa	2	
Number of bending magnets in the extraction line	2	
Number of quadrupoles in the extraction line	8	
Arc bending angle	90	Degrees
Number of bending magnets in the vertical arc	2	
Number of quadrupoles in the vertical arc	6	
Number of cavities for longitudinal phase space manipulation	5	
Number of quadrupoles in the in vivo beam line	4	
In vitro biological end stations		
Maximum input beam diameter	1.3	cm
Input beam energy spread	< 2	%
Input beam uniformity	< 5	%
Scintillating fibre layer thickness	0.25	mm
Air gap length	5	mm
Cell culture plate thickness	1.15	mm
Cell layer thickness	0.03	mm
Cell nutrient solution	15	mm
Number of end stations	2	
In vivo biological end station		
Maximum input beam diameter	1.3	cm
Input beam energy spread	< 2	%
Input beam uniformity	< 5	%
Beam options	Spot-scanning, passive scattering, micro-beam	

Accelerator




Staging

- Construction will be done in two stages.




Stage 1




Stage 2

- The goal is maximise scientific output.
 - Generate scientific output during construction of Stage 1.
 - Radiobiology programme using Stage 1 whilst constructing Stage 2.

Laser source





Principle of target normal sheath acceleration (TNSA).




Laser driven ion beam simulation using EPOCH.

- Produces intense beams and multiple species, e.g. proton and carbon ions.
 - Overcome space charge limit of conventional sources since beams are produced with energies $O(10)$ MeV.
- Issues to consider
 - Large energy spread.
 - Large divergence.
 - Beam stability, especially if laser operated near the limits of its specifications.




Capture




- The Gabor lens uses a plasma to generate a strong electrostatic focusing field.
- Focal point is energy dependent.
- Prototype development to study plasma stability, electron density and verify operation in relatively high vacuum.



Beam transport – Stage 1




- Optics design: BeamOptics and MADX.
- Particle tracking simulations: BDSIM and GPT.
- Energy deposition in the end station: BDSIM.



Beam transport – Stage 2


- Post acceleration done using an Fixed field accelerator (FFA).
 - Spiral FFA.
- Injection and extraction lines for the FFA.
- High energy arc for in vitro end station.
- In vivo beam line.



	40 MeV protons (Nominal)	127.4 MeV protons (Nominal)	127.4 MeV protons (Pessimistic)
RMS Emittance (ϵ_x, ϵ_y) [π mm mrad]	0.137	0.137	1.37
β [m] for a 1 mm spot size	0.46	0.46	0.039
β [m] for a 10 mm spot size	46	46	4.5
β [m] for a 30 mm spot size	410	410	40

Schedule

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names
1	Radiobiology	2743 days	Fri 14/02/20	Tue 20/08/30		Rbio_WPM_1[20%]
2	Radiobiology at partner facil	1443 days	Fri 14/02/20	Wed 27/08/25	3SF	Rbio_PDRA_1[50%],Rbio_PG_1[50%]
3	Radiobiology at LhARA	1300 days	Wed 27/08/25	Tue 20/08/30	50	Rbio_PDRA_1
4	System/near clinical aspects and outreach	2742 days	Mon 17/02/20	Tue 20/08/30		Rbio_PDRA_2,Outreach_Coord_1[20%]
5	Pre-LhARA: in collaboration with RFI SnL theme and other partners	1442 days	Mon 17/02/20	Wed 27/08/25	6SF	
6	LhARA: in collaboration with RFI SnL theme and other partners	1300 days	Wed 27/08/25	Tue 20/08/30	50	
7	LhARA Syr R&D plan	1300 days	Wed 01/04/20	Tue 25/03/25		
49	Construction	1670 days	Wed 30/08/23	Tue 22/01/30		
50	LhARA Stage 1 construction	520 days	Wed 30/08/23	Tue 26/08/25	60	FD_Eng_1,FD_Eng_2
51	LhARA Stage 2 construction	1300 days	Wed 29/01/25	Tue 22/01/30	13	FD_Eng_1,FD_Eng_2
52	Project office	2666.5 days	Mon 01/06/20	Tue 20/08/30	57SS	PO_ADMIN_1
53	Project leader	2666.5 days	Mon 01/06/20	Tue 20/08/30		
54	Project manager	2666.5 days	Mon 01/06/20	Tue 20/08/30		
55	WP managers	2666.5 days	Mon 01/06/20	Tue 20/08/30		
56	Gateway process	847 days	Mon 01/06/20	Tue 29/08/23		
57	GWO – Strategic assessment	0 days	Mon 01/06/20	Mon 01/06/20		
58	GW1 – Business justification	0 days	Fri 05/02/21	Fri 05/02/21	57FS+9 mons	
59	GW2 – Delivery strategy	0 days	Fri 15/10/21	Fri 15/10/21	58FS+9 mons,11	
60	GW3 – Investment decision	0 days	Tue 29/08/23	Tue 29/08/23	12FS+1 mon	



Five year R&D plan

