




Science and
Technology
Facilities Council

ITRF - LhARA

Power consumption &
Cost model for full infrastructure
ITRF WP2 & LhARA WP1.6

29th August 2023

Neil Bliss, UKRI-STFC-Daresbury Laboratory, Technology Department



Power Consumption Estimate

1272-pa1-pm-est-0001-v1.0-power-consumption-est-2023-08-23

- Work in progress
- Total power consumption estimated is 3580kW
- 2 x 2.5MVA transformers to be accounted for in full infrastructure cost model
- Line 4 is for a Solenoid only configuration
- Comparison required for Gabor Lense configuration
- Estimate probably on the high side and likely to reduce with more accurate information as the CDR and TDR phases develop.

	Technical Equipment	No of racks	Power/rack	Total load kW	Comment
1	Laser	4	12	48	Racks in annex room
2	Target	4	2	8	
3	Radio Frequency	5	n/a	186	
4	Gabor Lenses (solenoid only configuration)	14	n/a	658	
5	Pulse Power	4	n/a	14	Racks in accelerator
6	Power converters (magnets)	12	n/a	1411	
	<i>Controls & Instrumentation:</i>				
7	Laser				See 1.
8	Vacuum	6	2	9	2 racks in each RR
9	Diagnostics	9	1	9	3 racks in each RR
10	Personnel Safety	3	1	3	1 rack in each RR
11	Network/control	3	1	3	1 rack in each RR
12	RF Control & Auxiliaries	3	2	6	Located near RF Amplifiers
13	Motion Control	6	2	12	2 racks in each RR
14	End stations			0	
	Total number of racks	65		2367	
	<i>Services</i>				
15	Lighting			10	
16	Climate Control			110	
17	Chiller System			688	
18	Water pumps			60	
19	Compressed Air			5	
20	Offices/Laboratories			15	
	Total ancillary load (kW)			887	
	Total ITRF operational electrical load			3254	
	Total ITRF Electrical Infrastructure Requirement (10% contingency)			3580	

Full Infrastructure Cost Model

1272-pa2-pm-fin-0002-v1.0-ITRF-construction-cost-model-2023-08-24

- Work in progress
- Some lines based on pre-CDR with inflation and energy cost increases
- Laser cost update from recent ASTeC procurement exercise
- Building estimate from STFC Estates building cost model
- Integration requires an update. Power consumption tables will help
 - Electrical infrastructure
 - Cooling
 - HVAC
 - Vacuum
- R&D zero because prototyping is included in PA2 proposal
- Staff based on % of procurement. A more detailed breakdown is required later.

CBS	Description	Estimate
1	<i>Laser System</i>	£ 4,434,696
2	<i>Capture</i>	£ 1,190,000
3	<i>Stage 1 Accelerator Systems</i>	£ 1,265,000
4	<i>Stage 2 Accelerator Systems</i>	£ 10,190,000
5	<i>End Stations</i>	£ 1,797,900
6	<i>Integration</i>	£ 7,075,000
7	<i>R&D</i>	£ -
8	<i>Radiation Protection</i>	£ 2,810,000
9	<i>Building</i>	£ 22,254,694
10	<i>Installation</i>	£ 2,950,000
	<i>Total excluding VAT & contingency</i>	£ 53,967,290
	<i>Contingency (0%)</i>	£ -
	<i>Total excluding VAT</i>	£ 53,967,290
	<i>VAT</i>	£ 10,793,458
	<i>Total including VAT</i>	£ 64,760,748
11	<i>Staff (238 staff years @ £130K/sy) over 4 years</i>	£ 30,940,000
		£ 95,700,748
	Equipment - building	£ 73,446,054
	Staff to equipment ratio	42%