



University of
Strathclyde
Glasgow



Royal Charter
since 1964
Useful Learning
since 1796

PoPLaR Meeting @ Strathclyde

Update on proton source capabilities and beamline design in SCAPA
Bunker B

22nd November 2024


Dr. Ross Gray
ross.gray@strath.ac.uk

SCAPA: Scottish Centre for the Application of Plasma-based Accelerators

- Research is focused on the development and application of laser-driven particle acceleration.
- Can deliver high proton numbers, within the MeV energy range, at Hz level repetition rate.



Parameters	
Peak Power	$\geq 350 \text{ TW}$
FWHM pulse duration	$\leq 25 \text{ fs}$
Energy per pulse (on target)	<i>up to 7 J</i>
Pulse repetition rate	<i>1 Hz</i>
Temporal intensity contrast	$10^{10}:1 @ 100 \text{ ps}$ $10^8:1 @ 30 \text{ ps}$ $10^4:1 @ 2 \text{ ps}$ <i>ASE contrast $10^{10}:1$</i>
Central wavelength	<i>800 nm</i>
Beam quality Strehl ratio	≥ 0.85

SCAPA




Mechanism for laser-driven ion acceleration


Target Normal Sheath Acceleration (TNSA)



Proton beam characteristics





- Broad energy spectrum, up to a maximum cut off energy.



- Proton energy dependent beam divergence.




Update on Proton Source Parameters/Characterisation





- As reported during the last milestone meeting there were significant prepulses measured in the system which were limiting our proton energy and flux
- Offending prepulses have been removed, the contrast is significantly improved and there has been detailed characterisation of laser stability

Beamtime Updates

- Performed a 3-week experiment in June/July after laser contrast work in SCAPA and another run in September
- We have now measured protons > 15 MeV on SCAPA at up to 1 Hz repetition rate (typically 0.3 Hz)
- This has been cross calibrated with RCF dosimetry and we find with >10⁹ protons at 10 MeV.






Update on Proton Source Parameters/Characterisation







- More detailed measurements made of beam divergence and uniformity
- Uniformity is good at the relevant energies and divergence is as expected

Update on Proton Source Parameters/Characterisation




- Part of the experiment focused on measuring shot-to-shot stability of the proton spectrum
- On the TP this is around 8-10% but in reality it is around 2% as TP biases for beam structure and jitter
- We will be able to measure the spectrum on shot and so variation will be accounted for

September beam performance




- We performed an experiment in September 2024 which was not related to LhARA....but provided relevant measurements
- During the experiment the same shot was taken >100s of times to investigate the stability of the source
- While the laser parameters are stable the proton flux, max energy are seen to decrease while the specular (the fraction of reflected light increases).
- This was confirmed to be the burning of the pellicle at a rate faster than previously seen....this is concerning and needs to be resolved for continuous operations



Update on beamline design



Update on beamline design




Update on beamline design



- Progress has been made towards designing the PMQ beamline and cell station setup in SCAPA
- We would be looking to order parts in early January

Update on beamline design




- We are progressing with a simplified PMQ design
- 2 PMQs will be used with one being fixed in place and the other having XYZ and rotation about the central axis as degrees of freedom
- PMQ setup is designed so the magnets are detachable and moveable on a large stage
- This enables normal beam characterisation activity before PMQ use
- The cost of this design is still very high but delivers the flexibility in vacuum we need


Update on beamline model

- Developed a simple model to help us identify the optimum set of parameters to go for to reach the biological end goals
- Model uses Pstar CSDA ranges in water to work out the proton dose deposited at the end of the beamline
- Proton numbers derived from experimental data then we are free to vary:
 - Beam radius
 - Beamline transmission
 - Repetition rate
 - Energy-range of protons being considered
- There are a couple of potential solutions for >40 Gy/s (everything is a compromise!)

Update on beamline model




- This simple model suggests operating above 2 Hz with around 600 micron spot we could reach 40 Gy/s
- The model is quite simplistic at the moment. Doesn't take into account losses in the windows or the actual beam profile at the end of beamline
- SCAPA and the systems in Bunker B are not yet operating > 1Hz so this is very much a stretching target. The route to bring this closer is improving the proton flux in SCAPA (December source experiment)



Current system risks/status

- We have seen some growing damage on the parabola, gratings, final turning mirror and the pellicle
- The gratings are not replaceable in the short term, the final turning mirror is (we might switch to a dielectric mirror to improve longevity)
- We have a new parabola on order with delivery in the next couple months
- The pellicle performance is concerning and more work is needed to resolve
- All of these effects act to reduce energy on target and the quality of the focal spot reducing the performance of the source



Proposed Experiment Stages & Gateways

I. Design & Procurement

- Start of BP1 funding
- Order of PMQ XYZ stage (5-7 week delivery)
- Order of cell station vacuum parts (4 weeks delivery)
- Manufacture of thin window
- Manufacture of Oxford cell station

II. Assembly & Alignment

- Construction of the cell station and updated TP beamline
- Definition of an offline alignment line
- Construction and offline alignment of PMQ setup
- Install of PMQ system in vacuum chamber

III. Source Characterisation

- **1 week of SCAPA beamtime**
- Laser Beamline alignment (0.5 days)
- Source optimisation w/o PMQ (0.5 days)
- PMQ transmission, activation and debris test (0.5 days)
- Lanex/beam profiler measurement at end of beamline (1 day)
- PMQ position optimisation (0.5 days)
- RCF measurements through beamline (0.5 days)
- Full cell assembly RCF measurement (0.5 days)

IV. Radiobiology

- **2 weeks of SCAPA beamtime (with a gap between the alignment week)**
- Laser Beamline alignment (0.5 days)
- Source optimisation with PMQs (1 day)
- Dosimetry and source stability measurements (2 days)
- Cell irradiation (6.5 days) + regular dosimetry

Summary

- We are in a generally good position for the beam time. The proton source has been developed and optimised during experiments in July 2024 and September 2024...more to come in December 2024
- We have completed model calculations using this data and have identified a way to potentially achieve the required absorbed dose in good time
- The experiment will ramp up from beam and diagnostic optimisation, to dose calibration and then finally the irradiation.
- Potential issues are purchase of the PMQ parts, alignment of the beamline and the long term performance of the system due to pellicle damage



University of
Strathclyde
Glasgow



Royal Charter
since 1964
Useful Learning
since 1796